

FLOOR JOISTS LL = 40 PSF

DL = 15 PSF

### LIMIT STATES DESIGN INPUT PARAMETERS:

LL Deflection Limit I/360
TL Deflection Limit I/240
Vibration Checked YES
Ceiling NONE

Decking 5/8" OSB, Nailed & Glued ( 3/4" for 24" o.c.)

Straping NONE Blocking NONE

CODE NBCC 2010 / OBC 2012

MAXIMUM ALLOWABLE SPAN (centerline of bearing)						
Series	Depth	Joist spacing				
Selles		12" o.c.	16" o.c.	19.2" o.c.	24"o.c.	
	9-1/2"	16'-0"	15'-1"	14'-7"	14'-1"	
PJI 40	11-7/8"	17'-11"	16'-11"	16'-4"	15'-9"	
	14"	19'-9"	18'-5"	17'-8"	17'-1"	
	16"	21'-7"	20'-0"	19'-2"	18'-4"	
PJI 80	11-7/8"	19'-11"	18'-5"	17'-8"	17'-1"	
	14"	22'-1"	20'-6"	19'-6"	18'-8"	
	16"	24'-1"	22'-3"	21'-3"	20'-3"	

### NOTES:

- (a) Load Duration Factor = 1.0
- (b) Centerline of bearing span applicable to simple span residential floor construction with a des live load of 40 psf (1.92kPa) and dead load of 15 psf (.72kPa). The ultimate limit states are based on the factored loads of 1.25D + 1.50L. The serviceability limit states include the consideration for floor vibration and a live load deflection limit of the span/360 and a total load deflection limit of I/240.
- (c) Spans are based on composite floor with glue-nail sheathing meeting requirements for APA Rated Sheathing or APA Rated STURD-I-FLOOR conforming to PRP-108, PS1, PS2, CSA 0151,CSA 0437 with a minimum thickness of 5/8 inch for a joist spacing of 19.2" or less, or 23/32 inch for a joist spacing of 24". Adhesive shall meet the requirements given in ASTM D3498 or APA Specification AFG-01. No concrete topping, gypsum ceiling, or bridging element was assumed.
- (d) Minimum bearing length shall be 1-3/4" for the end bearings.
- (e) Refer to PJI Installation Guide and Product Information Guide for framing details, web hole chart, and storage and handling instructions.
- (f) Do not cut or notch flanges. Do not violate web hole chart rules.

90243759



## **Anthony Forest Products PJI JOIST SPAN Chart**

FLOOR JOISTS LL = 40 PSF DL = 15 PSF

## LIMIT STATES DESIGN INPUT PARAMETERS:

LL Deflection Limit I/360
TL Deflection Limit I/240
Vibration Checked YES
Ceiling NONE

Decking 5/8" OSB, Nailed & Glued ( 3/4" for 24" o.c.)

Straping NONE

Blocking ONE ROW @ Center
CODE NBCC 2010 / OBC 2012

MAXIMUM ALLOWABLE SPAN (centerline of bearing)						
Series	Depth	Joist spacing				
Selles		12" o.c.	16" o.c.	19.2" o.c.	24"o.c.	
	9-1/2"	16'-11"	16'-0"	15'-6"	14'-10"	
D II 40	11-7/8"	19'-4"	18'-0"	17'-5"	16'-10"	
PJI 40	14"	21'-7"	20'-1"	19'-3"	18'-5"	
	16"	23'-8"	22'-0"	21'-1"	20'-2"	
PJI 80	11-7/8"	21'-6"	19'-11"	19'-1"	18'-3"	
	14"	24'-0"	22'-3"	21'-3"	20'-4"	
	16"	26'-3"	24'-4"	23'-3"	22'-3"	

### NOTES:

- (a) Load Duration Factor = 1.0
- (b) Centerline of bearing span applicable to simple span residential floor construction with a design live load of 40 psf (1.92kPa) and dead load of 15 psf (.72kPa). The ultimate limit states are based on the factored loads of 1.25D + 1.50L. The serviceability limit states include the consideration for floor vibration and a live load deflection limit of the span/360 and a total load deflection limit of I/240.
- (c) Spans are based on composite floor with glue-nail sheathing meeting requirements for APA Rated Sheathing or APA Rated STURD-I-FLOOR conforming to PRP-108, PS1, PS2, CSA 0151,CSA 0437 with a minimum thickness of 5/8 inch for a joist spacing of 19.2" or less, or 23/32 inch for a joist spacing of 24". Adhesive shall meet the requirements given in ASTM D3498 or APA Specification AFG-01. No concrete topping, or gypsum ceiling element was assumed.
- (d) Minimum bearing length shall be 1-3/4" for the end bearings.
- (e) Refer to PJI Installation Guide and Product Information Guide for framing details, web hole chart, and storage and handling instructions.
- (f) Do not cut or notch flanges. Do not violate web hole chart rules.



FLOOR JOISTS LL = 40 PSF DL = 15 PSF

### LIMIT STATES DESIGN INPUT PARAMETERS:

LL Deflection Limit I/360
TL Deflection Limit I/240
Vibration Checked YES
Ceiling NONE

Decking 5/8" OSB, Nailed & Glued ( 3/4" for 24" o.c.)

Straping NONE

Blocking TWO ROWS @ 24" Center CODE NBCC 2010 / OBC 2012

MAXIMUM ALLOWABLE SPAN (centerline of bearing)						
Series	Depth	Joist spacing				
Selles		12" o.c.	16" o.c.	19.2" o.c.	24"o.c.	
	9-1/2"	17'-6"	16'-7"	16'-0"	14'-10"	
PJI 40	11-7/8"	20'-4"	18'-11"	18'-1"	17'-4"	
	14"	22'-10"	21'-3"	20'-3"	19'-0"	
	16"	25'-2"	23'-4"	22'-3"	20'-5"	
PJI 80	11-7/8"	22'-7"	20'-11"	19'-11"	19'-0"	
	14"	25'-5"	23'-6"	22'-5"	21'-4"	
	16"	27'-11"	25'-11"	24'-8"	23'-5"	

### NOTES:

- (a) Load Duration Factor = 1.0
- (b) Centerline of bearing span applicable to simple span residential floor construction with a desi live load of 40 psf (1.92kPa) and dead load of 15 psf (.72kPa). The ultimate limit states are based on the factored loads of 1.25D + 1.50L. The serviceability limit states include the consideration for floor vibration and a live load deflection limit of the span/360 and a total load deflection limit of I/240.
- (c) Spans are based on composite floor with glue-nail sheathing meeting requirements for APA Rated Sheathing or APA Rated STURD-I-FLOOR conforming to PRP-108, PS1, PS2, CSA 0151,CSA 0437 with a minimum thickness of 5/8 inch for a joist spacing of 19.2" or less, or 23/32 inch for a joist spacing of 24". Adhesive shall meet the requirements given in ASTM D3498 or APA Specification AFG-01. No concrete topping, or gypsum ceiling element was assumed.
- (d) Minimum bearing length shall be 1-3/4" for the end bearings.
- (e) Refer to PJI Installation Guide and Product Information Guide for framing details, web hole chart, and storage and handling instructions.
- (f) Do not cut or notch flanges. Do not violate web hole chart rules.



FLOOR JOISTS LL = 40 PSF

DL = 15 PSF

### LIMIT STATES DESIGN INPUT PARAMETERS:

LL Deflection Limit I/360
TL Deflection Limit I/240
Vibration Checked YES

Ceiling 1/2" Gypsum

Decking 5/8" OSB, Nailed & Glued ( 3/4" for 24" o.c.)

Straping NONE Blocking NONE

CODE NBCC 2010 / OBC 2012

MAXIMUM ALLOWABLE SPAN (centerline of bearing)						
Series	Depth	Joist spacing				
		12" o.c.	16" o.c.	19.2" o.c.	24"o.c.	
	9-1/2"	16'-5"	15'-7"	15'-0"	14'-6"	
PJI 40	11-7/8"	18'-7"	17'-5"	16'-10"	16'-3"	
PJI 40	14"	20'-7"	19'-2"	18'-5"	17'-8"	
	16"	22'-5"	20'-11"	20'-0"	19'-2"	
PJI 80	11-7/8"	20'-7"	19'-1"	18'-3"	17'-6"	
	14"	22'-10"	21'-2"	20'-3"	19'-4"	
	16"	24'-11"	23'-1"	22'-1"	21'-0"	

### NOTES:

- (a) Load Duration Factor = 1.0
- (b) Centerline of bearing span applicable to simple span residential floor construction with a desi live load of 40 psf (1.92kPa) and dead load of 15 psf (.72kPa). The ultimate limit states are based on the factored loads of 1.25D + 1.50L. The serviceability limit states include the consideration for floor vibration and a live load deflection limit of the span/360 and a total load deflection limit of I/240.
- (c) Spans are based on composite floor with glue-nail sheathing meeting requirements for APA Rated Sheathing or APA Rated STURD-I-FLOOR conforming to PRP-108, PS1, PS2, CSA 0151,CSA 0437 with a minimum thickness of 5/8 inch for a joist spacing of 19.2" or less, or 23/32 inch for a joist spacing of 24". Adhesive shall meet the requirements given in ASTM D3498 or APA Specification AFG-01. No concrete topping, or bridging element was assumed.
- (d) Minimum bearing length shall be 1-3/4" for the end bearings.
- (e) Refer to PJI Installation Guide and Product Information Guide for framing details, web hole chart, and storage and handling instructions.
- (f) Do not cut or notch flanges. Do not violate web hole chart rules.



FLOOR JOISTS LL = 40 PSF

DL = 15 PSF

### LIMIT STATES DESIGN INPUT PARAMETERS:

LL Deflection Limit I/360
TL Deflection Limit I/240
Vibration Checked YES

Ceiling 1/2" Gypsum

Decking 5/8" OSB, Nailed & Glued ( 3/4" for 24" o.c.)

Straping NONE

Blocking ONE ROW @ Center
CODE NBCC 2010 / OBC 2012

MAXIMUM ALLOWABLE SPAN (centerline of bearing)						
Series	Depth	Joist spacing				
		12" o.c.	16" o.c.	19.2" o.c.	24"o.c.	
	9-1/2"	18'-2"	17'-1"	16'-0"	14'-10"	
PJI 40	11-7/8"	21'-4"	19'-11"	19'-1"	17'-4"	
	14"	24'-0"	22'-5"	21'-3"	19'-0"	
	16"	26'-5"	24'-8"	22'-10"	20'-5"	
PJI 80	11-7/8"	23'-6"	21'-10"	20'-10"	19'-10"	
	14"	26'-4"	24'-7"	23'-5"	22'-3"	
	16"	29'-0"	27'-0"	25'-9"	24'-6"	

### NOTES:

- (a) Load Duration Factor = 1.0
- (b) Centerline of bearing span applicable to simple span residential floor construction with a deslive load of 40 psf (1.92kPa) and dead load of 15 psf (.72kPa). The ultimate limit states are based on the factored loads of 1.25D + 1.50L. The serviceability limit states include the consideration for floor vibration and a live load deflection limit of the span/360 and a total load deflection limit of I/240.
- (c) Spans are based on composite floor with glue-nail sheathing meeting requirements for APA Rated Sheathing or APA Rated STURD-I-FLOOR conforming to PRP-108, PS1, PS2, CSA 0151,CSA 0437 with a minimum thickness of 5/8 inch for a joist spacing of 19.2" or less, or 23/32 inch for a joist spacing of 24". Adhesive shall meet the requirements given in ASTM D3498 or APA Specification AFG-01. No concrete topping element was assumed.
- (d) Minimum bearing length shall be 1-3/4" for the end bearings.
- (e) Refer to PJI Installation Guide and Product Information Guide for framing details, web hole chart, and storage and handling instructions.
- (f) Do not cut or notch flanges. Do not violate web hole chart rules.



FLOOR JOISTS LL = 40 PSF

DL = 15 PSF

### LIMIT STATES DESIGN INPUT PARAMETERS:

LL Deflection Limit I/360
TL Deflection Limit I/240
Vibration Checked YES

Ceiling 1/2" Gypsum

Decking 5/8" OSB, Nailed & Glued ( 3/4" for 24" o.c.)

Straping NONE

Blocking TWO ROWS @ 24" Center CODE NBCC 2010 / OBC 2012

MAXIMUM ALLOWABLE SPAN (centerline of bearing)						
Series	Depth	Joist spacing				
		12" o.c.	16" o.c.	19.2" o.c.	24"o.c.	
	9-1/2"	18'-11"	17'-1"	16'-0"	14'-10"	
PJI 40	11-7/8"	22'-7"	20'-6"	19'-3"	17'-4"	
	14"	25'-8"	23'-3"	21'-3"	19'-0"	
	16"	28'-6"	25'-1"	22'-10"	20'-5"	
PJI 80	11-7/8"	25'-8"	23'-10"	22'-7"	20'-11"	
	14"	29'-3"	27'-2"	25'-8"	23'-9"	
	16"	32'-9"	30'-3"	28'-7"	26'-5"	

### NOTES:

- (a) Load Duration Factor = 1.0
- (b) Centerline of bearing span applicable to simple span residential floor construction with a deslive load of 40 psf (1.92kPa) and dead load of 15 psf (.72kPa). The ultimate limit states are based on the factored loads of 1.25D + 1.50L. The serviceability limit states include the consideration for floor vibration and a live load deflection limit of the span/360 and a total load deflection limit of I/240.
- (c) Spans are based on composite floor with glue-nail sheathing meeting requirements for APA Rated Sheathing or APA Rated STURD-I-FLOOR conforming to PRP-108, PS1, PS2, CSA 0151,CSA 0437 with a minimum thickness of 5/8 inch for a joist spacing of 19.2" or less, or 23/32 inch for a joist spacing of 24". Adhesive shall meet the requirements given in ASTM D3498 or APA Specification AFG-01. No concrete topping element was assumed.
- (d) Minimum bearing length shall be 1-3/4" for the end bearings.
- (e) Refer to PJI Installation Guide and Product Information Guide for framing details, web hole chart, and storage and handling instructions.
- (f) Do not cut or notch flanges. Do not violate web hole chart rules.